May 7, 2015

COMMUNITY NOTICE
Port Moody

Construction Activities at Seaview Drive and Clarke Road

The tunnel boring machine (TBM) remains underneath Clarke Road at Seaview Drive as part of planned maintenance to inspect and replace the cutterhead tools. Since April 9, crews have been continuing to strengthen and stabilize the soil (jet grouting) in front of the TBM to allow maintenance to resume.

We apologize for the ongoing inconvenience this is causing your community and thank you for your patience. We are doing everything we can to complete this work as quickly as possible. This work has taken longer than anticipated due to the challenging ground conditions in this area.

The jet grouting operations will continue over the next few weeks until we are certain it will be safe for the crews to enter the chamber behind the cutterhead. Crews will then inspect and change the cutterhead tools on the face of the TBM approximately 40 metres below the surface. The changing of the cutterhead tools will take approximately one month and then tunnel boring will resume. Please note that construction schedules are subject to change.

WHAT TO EXPECT

Jet Grouting Operations

- Hours of work will be 7 a.m. to 10 p.m. Monday through Saturday and 10 a.m. to 6 p.m. on Sunday (if required). Every effort is being made to complete work as close to 8 p.m. in the evening as possible; however, work may extend until 10 p.m. if required.
- Drill rigs will be on site within the secure work area on Clarke Road to inject grout until mid-to-late May.
- Noise related to construction activities will include pumps, generators, air compressors, hydro-vaccing, cement trucks and the use of heavy machinery.

Cutterhead Tool Inspection and Maintenance

- The inspection and replacement of the cutterhead tools will occur below the surface and will be ongoing 24 hours a day.
- Construction fencing will remain on the roadway while this work is underway and some equipment may be left within the fenced area.
- Localized dewatering wells will be used on the west side of Clarke Road at Seaview Drive to temporarily lower the ground water levels in front of the TBM while the cutterhead tools are being changed. All groundwater that is removed will be tested and disposed of in accordance with appropriate authority regulations.

(Continued on Page 2)

ABOUT EGRT CONSTRUCTION

EGRT Construction has been awarded the contract to design and build the Evergreen Line.

For more information about the Evergreen Line Project, please visit www.evergreenline.gov.bc.ca.

CONTACT US

To find out more, or to receive traffic updates:

Traffic Information Line (available 24 hours, 7 days a week): 604-927-2080
Email: info@evergreenline.gov.bc.ca
Facebook: www.facebook.com/evergreenline

May 7, 2015

COMMUNITY NOTICE
Port Moody

(Continued from page 1)

- Crews will be operating a generator throughout the night as part of the dewatering process, but it will be covered to minimize noise and disruption to nearby residents.

TRAFFIC PATTERNS

- Existing traffic patterns will be maintained as the surface work continues. Lane closures on Clarke Road at Seaview Drive will remain in effect.

Safety

- The speed limit on Clarke Road will remain reduced from 50 km/h to 40 km/h while work is underway.
- Digital speed warning boards will continue to warn drivers if they are travelling too fast and additional enforcement will be in effect for the duration of construction on this section of roadway.
- Traffic control personnel will continue to be on-site at Clarke Road and Seaview Drive during working hours to assist drivers and local residents.
- Drivers, cyclists and pedestrians are asked to watch for construction and detour signs, observe posted speed limits, proceed with caution and follow the directions of traffic control personnel.

If you have comments or questions about the Evergreen Line Rapid Transit Project, please call the Evergreen Project Office at (604) 927-4452 or email info@evergreenline.gov.bc.ca. To contact EGRT Construction, the contractor who is building the Evergreen Line, please call 604-927-2080, available 24 hours a day, 7 days a week.

ABOUT EGRT CONSTRUCTION

EGRT Construction has been awarded the contract to design and build the Evergreen Line.

For more information about the Evergreen Line Project, please visit www.evergreenline.gov.bc.ca.

CONTACT US

To find out more, or to receive traffic updates:

Traffic Information Line (available 24 hours, 7 days a week): 604-927-2080
Email: info@evergreenline.gov.bc.ca
Facebook: www.facebook.com/evergreenline